No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
14	Ventilators with wooden frame glazed shutters, etc., complete	S.ft.	..	12	
15	Plastering with mortar for walls	Sqr.	..	72·87	
16	Flooring with 1½″ metal concrete with cement mortar over 4″ metal concrete in lime mortar, plastering with cement mortar and red ochre with lines, cut, etc., complete	,,	..	7·74	
17	Teak wood eave boards ¾′ ornamental ..	R.ft.	..	·86	
18	Painting doors and windows with two coats of chocolate paint (mixed and applied as per Bombay specifications)	Sqr.	..	9·12	
19	Pointing the basement with cement mortar ..	,,	..	1·50	
20	White washing ½″ as per plastering	,,	..	36·86	
21	Colour washing	,,	..	36·86	

M. K. RAJAM IYENGAR,
Executive Engineer.

WATER SUPPLY DIVISION.

Notification dated 5th March 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water Supply Division, Bangalore, on 1st April 1940 upto 3 P.M. for constructing R.C.C. tank of 1,50,000 gallons capacity in the newly formed extension, Subedar Chattram Road, Bangalore, as per specifications noted below. The work should be completed within three months from the date of acceptance of tender.

2. Tenders should be submitted along with printed specification form which may be obtained from the Executive Engineer, on a payment of Re. 0-4-0.

3. Each tender must be accompanied by a chellan for having credited to the Treasury a deposit amount of Rs. 750 (Rupees seven hundred and fifty only) under "17. (*a*) P. W. deposits," and be superscribed "Tender for constructing R.C.C. tank of 1,50,000 gallons capacity in the newly formed extension, Subedar Chattram Road, Bangalore City", in default of which tenders will be rejected.

4. The final acceptance of any tender will rest with the Executive Engineer who does not bind himsef to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Within eight days of the acceptance of tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

6. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's office in due course. No enquiry regarding the acceptance or rejection of tender will receive any reply.

7. After accepting one of the tenders, the earnest money on rejected tenders will be returned.

8. Rates once tendered will not be enhanced on any account.

9. Rates for non-tendered and non-estimated items shall be those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

10. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurement, quality of work, etc., and in all disputes of any kind, the decision of the Executive Engineer, will be final and legally binding.

Specification.

(1) The tank should be circular in shape, 50′ outside diameter and 15′ high from the floor level. This is on the ground surface.

(2) The tank should be R.C.C. and the following factors shall be taken into consideration in the design to be adopted:—

(*a*) Tensile strength of steel bars 12,000 lb. per square inch.

(*b*) While calculating for the circular side walls full bursting pressure shall be considered.

(*c*) The proportion of mixture for all portions except the roof shall be 1 : 1½ : 3 and for the roofing it shall be 1 : 2 : 4.

(3) Suitable dust proof ventilators should be provided for in the roofing.

(4) The roofing shall be flat with two man-hole covers each 3′×3′ complete with mild steel lids, hinges, hasp and staple suitable for locking.

(5) One water level indicator complete with float gauge board pointer, flexible wire, guide pulleys, etc., shall be included in the tender.

(6) The outer surface of the side wall except the roofing and inside of the parapet should be finished with cream-coloured cement.

(7) *Nature of foundation.*—Gravel, with boulder out crops.

(8) All the pipe fittings will be supplied by the Department.

(9) A small parapet to the tank of suitable design should be provided for in the tender.

(10) No lumpsum quotations will be considered. Plans and estimates with detail drawings showing various reinforcements should accompany the tender. The estimate should give the quantities, rates and cost of each item. Any variation in the quantity will be paid for at the rates as per the detail estimate.

(11) Non-tendered items of work will be paid for after working out the data with not more than 10 per cent profit for the contractor.

(12) Cement to be used should be purchased through the Department.

M. K. NARASIMHA IYER,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification dated 24th February 1940.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for restoring Kayamgutta Kattariguppe Kannerkatte Minor Tank, Reg. No. 62 of Bangalore Taluk, published on pages 428-430, Part VI of the *Mysore Gazette*, dated 29th February 1940.

The last date for the receipt of the tender is 2 P.M. on 16th March 1940. Duplicate chellan for having credited the deposit amount of Rs. 210 into the Treasury under "17 (*a*) P. W. Deposits" should accompany each tender.

Abstract Notification dated 24th February 1940.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for restoring Dandidass Kodagehalli Tank, Reg. No. 192 of Dodballapur Taluk, published in pages 430-432, Part VI of the *Mysore Gazette*, dated 29th February 1940.

The last date for the receipt of the tender is 2 P.M. on 18th March 1940. Duplicate chellan for having credited the deposit amount of Rs. 300 into the Treasury under "17-(*a*) P. W. Deposits" should accompany each tender.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notice dated 5th March 1940.

The attention of the public is invited to the notification calling for tenders for the work of "Providing Sanitary fittings in the newly constructed latrine attached to the Agricultural Office, Bangalore," published in Part VI, pages 522-524 of the *Mysore Gazette*, dated 7th March 1940.

The last date of receiving tenders is fixed on 18th March 1940.

Notification dated 4th March 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 19th March 1940, for the drainage work of the mode moats around the fort in Periyapatna Town to prevent breading of mosquitoes. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.